

Poly-Upgrading your SoundStation IP Firmware

Support Information

The Polycom SoundStation IP line has reached End of Life, (EOL) Status. This means Poly is no longer releasing software updates for this series. Please make sure your phone is upgraded to the latest software before upgrading to our new system.

Software 4.0.15.1009

IP321/331	IP335	IP430	IP450	IP501	IP550	IP560
IP601	IP650	IP670	IP4000	IP5000	IP6000	IP7000

This procedure was performed using an IP550 conference phone. The process is the same for any phone in the list above.

Identifying the Current Firmware Version

1. Press the Menu key
2. Select Status
3. Select Platform
4. Select Application
5. Select Main
6. The phone will display the Version of the current Firmware. If the version is 4.0.15.1009 you do not need to upgrade the telephone.


Obtaining the IP Address of the Telephone

1. Press the Menu key
2. Select Status
3. Select Network

4. Select TCP/IP Parameters
5. Record the IPV4 address which will be entered in your browser

Logging into the Telephones Web Browser


1. Using Edge or Chrome enter the IP address from the telephone into the address bar of your browser in the form of https://xxx.xxx.xxx.xxx




2. Select Admin as the user and enter the telephones password. If you do not have the password for your telephone please open a ticket or call support to request the password.
3. Click Submit

Upgrading a SoundStation IP

1. From the home select the Utilities Menu then Software Upgrade.



2. From the Software Upgrade page click Check for Updates



3. Select software version 4.0.15.1047 from the "Software available at Polycom Server" drop down.
4. Click Install
5. A confirmation window will pop-up asking you to confirm the upgrade, click Yes
6. At the License Agreement pop-up click Accept.
7. A final Informational pop-up window will appear informing you the phone will reboot and update, click OK
8. Once the phone reboots it will begin the upgrade

process. Please be patient the upgrade takes around 5 minutes.

9. Once the upgrade is complete recheck the Firmware version to ensure the upgrade is complete.

Version01.11172021